

KANSAS

*al*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1972

CONSERVATION DIVISION  
Wichita, Kansas

15-147-20041-00-00

Operator's Full Name Don H. Peaker

Complete Address Box 1595 Pueblo, Colorado 81002

Lease Name Portenier Well No. 1

Location NW NW NE Sec. 12 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3609'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 9:30 A Day 13 Month 10 Year 1972

The above well was plugged as follows:

Total Depth 3609' 8 5/8 csg set at 214' cwc Cmt. Mat. 50-50 poz cmt W/6% gel.

4 1/2 csg set at 3608' cw 100 sk cmt.

4 1/2 csg perf. (3444-3450)

Filled 4 1/2 csg W/sd (3425-3609) Dumped 4 sk cmt W/dump bailer. (3390-3425)

Cutoff & recovered 2070' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/ 500 lbs hulls, - 70 sk cmt, -

10 sk gel & water - released 8 5/8 plug & pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. F. Mussey  
Well Plugging Supervisor

DATE 10/19/72  
INV. NO. 6473-W