

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don H. Peaker 15-147-20053-00-00

Complete Address Box 1595 Pueblo, Colorado 81002

Lease Name A. Adee Well No. 1

Location NE SE NE Sec. 11 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3630

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 12:15 P Day 23 Month 7 Year 1970

The above well was plugged as follows:

Total Depth 3630' 8 5/8 csg set at 203' cwc

4 1/2 csg set at 3630' cw 200 sk cmt

4 1/2 csg PBTD 3592' Perf. (3533-3577) (3393-3397)

Filled 4 1/2 csg W/sl (3350-3592) Dumped 4 sk cmt W/dump bailer. (3300-3350)

Cutoff and recovered 2590' of 4 1/2 csg.

Pumped 15 gel W/5 sk hulls, 70 sk reg poz 6%, 15 sk gel, plug and 55 sk reg poz 6%.

Cmt. (0-230) Gel (230-740) Cmt (740-940) Gel (940-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 7/28/70

INV. NO. 2294-W