

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-30185-00-00

FILE NO. 119-16

LOCATION SW SW NE

SEC. 10 TWP. 1 RGE. 18

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Heth

Operator Natl Associated Pet Co Address Ritz Bldg

Field \_\_\_\_\_ County Phillips

Total Depth 3445 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 186' circulated with cement - 5 1/2" at 3443' with 150 sax  
cement behind. Top perforation at 3389'.

Filled with chat to 3370', set 5 sax cement with dump bailer,

pulled 2700' 5 1/2", filled hole with mud to 186', set rock and

20 sax cement, filled with mud to 30', set rock and 10 sax

cement to bottom cellar.

PLUGGING

FILE SEC 10 TWP 1 RGE 18

BOOK PAGE 119 LINE 16

*Edmond Petty*

District Conservation Agent

Date

11-19-51

NOV 21 1951

CONSERVATION DIVISION  
Wichita, Kansas