

KANSAS

AP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Lowell Keesee 15-147-20055-00-00
Complete Address 785 3rd St. Phillipsburg, Kansas 67661
Lease Name Chestnut Well No. 1
Location SW SW SW Sec. 11 Twp. 1 Rge. (E) (W) 18
County Phillips Total Depth 3533
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling
Address Box 364 Great Bend, Kansas License No. 399
Operation Completed: Hour 11:30 A Day 29 Month 7 Year 1970

The above well was plugged as follows:

Total Depth 3533' 8 5/8 csg set at 215' cwc 165 sk.
4 1/2 csg set at 3532' cw 140 sk cmt.
4 1/2 csg PBTD 3501' Perf. (3394-3396)
Filled 4 1/2 csg W/sd (3350-3501) Dumped 4 sk cmt W/dump bailer. (3315-3350)
Cutoff and recovered 2730' of 4 1/2 csg.
Pumped thru 8 5/8 plug container with 15 sk gel W/3 sk hulls, 70 sk poz 6% gel,
15 sk gel W/2 sk hulls, plug and 55 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/31/70
INV. NO. 2314-W

Signed: *Lowell Keesee*
Well Plugging Supervisor