


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-147-00143-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Phillips County. Sec. 8 Twp. 1S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines NW 1/4 NW 1/4 SE 1/4
Lease Owner Livingston Oil Company
Lease Name Knape Well No. 1
Office Address P. O. Box 1797 Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 8 19 59
Application for plugging filed February 8 19 59
Application for plugging approved February 8 19 59
Plugging commenced February 8 19 59
Plugging completed February 8 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3783 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	203'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 195' with heavy mud set plug with 1/3 sack hulls and 20 sacks cement. Filled hole to 30' with mud and set plug with 1/3 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
William J. Duckett (employee of ~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William J. Duckett
915 Union Center Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of February, 19 59

My commission expires August 20, 1960
A. R. Derrington (A. R. Derrington) Notary Public.

PLUGGING
FILE SEC 0 T. I. R18W
BOOK PAGE 17 LINE 6

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-147-00143-00-00

Company- LIVINGSTON OIL CO.
Farm- Knappe No. 1

SEC. 8 T. 1 R. 18W
NW NW SE

Total Depth. 3783'
Comm. 1-26-59 Comp. 2-8-59
Shot or Treated.
Contractor. Lewis Drlg. Co.
Issued. 5-28-60

County Phillips
KANSAS



Elevation. 2063 RB

CASING:
10 3/4" 200" cem.w/110 sx.

Production. Dry

Figures Indicate Bottom of Formations.

limestone, chalky & cherty	3079-83	DST #1	3280-98
limestone, very chalky	3110-15	DST #2	3310-20
limestone, chalky	3141-48	DST #3	3328-40
limestone	3188-93	DST #4	3337-62
limestone, chalky	3210-14	DST #5	3360-92
limestone, partly cherty	3262-66	DST #6	3403-20
limestone, no free oil	3280-86	DST #7	3416-36
limestone, show free oil	3310-12	DST #8	3433-58
" " " "	3316-18	DST #9	3454-3550
limestone, no free oil	3328-30		
" " " "	3345-47		
limestone, gray-yellow	3355-57		
limestone, partly chalky	3366-69		
limestone, cherty	3411-15		
limestone, no free oil	3428-31		
limestone, broken xlyn. & chalky	3441-50		
limestone	3471-75		
limestone	3490-93		
limestone, chalky	3589-3632		
limestone, chalky grading to red- brown sandy shale	3638-45		
shale, brn & red, & chert Yellow & white	3655		
shale, silty	3670		
chert with interbedded red shale and weathered limestone	3700		
dolomite	3706		
shale, gray, green, yellow	3716		
dolomite, gray-yellow, cherty & shaley	3726		
shale, green sandy	3735		
cherty dolomite	3741		
shale with lime strks.	3750		
dolomite, pink-red, silty	3757		
shale, gray-black to dark brown, some chalky lime	3762		
dolomite, red-pink & gray, cherty	3768		
dolomite	3777		
shale, dull green-gray	3783		
Total Depth			

TOPS:	Driller:	E. Log
Cimmerron Anhydrite	1850	
Topeka Lime	3019	3024
Heebner	3229	3228
Toronto	3261	3262
Lansing-Kansas City	3278	3277
Basal Kansas City	3500	3498
Marmaton Lime	3589	
Conglomerate Shale	3645	
Conglomerate Chert	3670	
Weathered Viola	3700	