


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-147-00143-00-01 Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Phillips County, Sec. 8 Twp. 1 Rge. 18 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Leland Baird
Lease Name Knappe Well No. #1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10-25-73 19
Plugging completed 10-29-73 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3583' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3539'	2422.11'
				10 3/4"	203'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 3275' - sanded back to 3250'. Mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 3 sacks hulls - 15 sacks gel. 2 sacks hulls - 70 sacks cement and 15 sacks gel. Released plug and displaced with 80 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas (Address)

Subscribed and Sworn to before me this 30 day of October, 1973

My commission expires October 1976
Notary Public

15-147-00143-00-01

T.D. 3583'
5 1/2 - 3539 w/ 270 sk
10 3/4 - 203' em
PB 3505
Purf 3310-12-14
3470-71-73
set plg 3275 - 25' sd
B'5 sk
359 e1 - 5 hulls - 150 P03
67

B & B DRILLING, INC.
207 Petroleum Building
Wichita, Kansas 67202

April 22, 1971

RECEIVED
STATE OF KANSAS COMMISSION
SEP 26 1973
GENERAL INVESTIGATIVE DIVISION
KANSAS

15-147-00143-00-01

DRILLERS LOG

Re: Leland Baird #1 Knappe Washdown
NW NW SE Section 8-1S-18W
Phillips County, Kansas

OPERATOR: Leland R. Baird
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: April 17, 1971
COMPLETED: April 18, 1971
TOTAL DEPTH: 3583'

0	10	Open Hole
10	35	Cement
35	185	Open Hole
185	203	Cement
203	2017	Wash Doen
2017	3583	Wash Down
3583		Total Depth

Ran 5 1/2" @ 3539' w/50 sx poz 50/50 2% gel & 12.5#
Gilsonite - 220 Port @% gel & 8% CFR -2

We certify the above and foregoing to be true and
Correct copy of the log on the #1 Knappe, located in
Phillips County, Kansas.

B. J. Fisher President

Alma A. Nuseer Notary Public

Subscribed and sworn to before me this 22nd day
of April, 1971. My commission expires May 31, 1974