


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Phillips County, Sec. 4 Twp. 15 Rge. 13 (X) (W)
Location as "NE/CNW/SW" or footage from lines SW NW SW
Lease Owner C. R. Moffitt
Lease Name Walker #2 Well No.
Office Address 809 Bitting Bldg. Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 5-30-59 19.
Application for plugging filed March 6 19.63
Application for plugging approved March 7 19.63
Plugging commenced March 21 19.63
Plugging completed March 23 19.63
Reason for abandonment of well or producing formation Decline in production

If a producing well is abandoned, date of last production 10-22 19.62
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing - K.C. Depth to top Bottom Total Depth of Well 3530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	169	cemented
				5 1/2	3528	2720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3445 to 3490, run 4 sacks of cement from 3490 to 3470. Shot at 2805

Pumped 11 sacks of jel mud and 20 sacks of cement at 550'
Pumped 20 sacks of cement at 200' and run 10 sacks of cement from 30' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 114, Ellinwood, Kansas.

STATE OF Kansas COUNTY OF Sedgwick, ss.
C. R. Moffitt (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Moffitt
809 Bitting Bldg. Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 1963

My commission expires August 10, 1965 Virginia Mundell Notary Public.

G. R. Moffet - Owner

Sierra Petroleum Co - Contr.

WALKER #2

SW 1/4 Sec 4-15-18W
Phillips County, Kansas

Total Depth: 3530'

Elev: 2075 KB

Comm: 5/21/59
Comp: 5/30/59

15-147-19015-00-00

Casings:

3 5/8 @ 160'
3 1/2 @ 3525'

Cement:

with 135 sbs cement
with 150 sbs cement

FORMATION

DEPTH

Clay	60
Shale	125
Shale & shells	370
Sand & shale	965
Sand, shale & shells	1460
Shale & Red Bed	1990
Anhydrite	1975
Shale & Red Bed	2245
Lime & shale	3205
Lime	3530

No tops available

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 1st day of June, 1959.

Margie Cooper
Notary Public

My commission expires: 1-30-61.