


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-147-19019-00-00 Form CP-4
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 5 Twp. 15 Rge. 18 (X) (W)
Location as "NE/CNW/SW" or footage from lines. NE NE SE
Lease Owner C. R. Moffitt
Lease Name Pretzer Well No. 1
Office Address 809 Bitting Bldg, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-28 19 59
Application for plugging filed March 6 19 63
Application for plugging approved March 7 19 63
Plugging commenced March 21 19 63
Plugging completed March 23 19 63
Reason for abandonment of well or producing formation Decline in production

If a producing well is abandoned, date of last production March 19 1963
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing-K.C. Depth to top Bottom Total Depth of Well 3480' Feet
Show depth and thickness of all water, oil and gas formations. No tops.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	183'	cemented
				5 1/2	3478'	2820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 3443 to 3400, run 4 sacks of cement from 3400 to 3380. Shot at 2801.
Pumped 20 sacks of cement and 18 sacks of mud at 550' and pumped 20 sacks of cement at 200' and run 10 sacks of cement from 30' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 114, Ellinwood, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Moffitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Moffitt
809 Bitting Bldg, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 1963

My commission expires August 10, 1965
Virginia Mundell, Notary Public.

C. R. Moffit - Owner

FRITZER #1

Total Depth: 3430'

Comm: 7/20/59

Comp: 7/28/59

Casing:

8 5/8 @ 183'

5 1/2 @ 3473

Cement:

with 125 sks cement

600 gal Letex

FORMATION

DEPTH

Surface soil & clay	30
Shale	100
Shale & shells	1300
Sand	1405
Red Bed	1500
Red Bed & Shale	1901
Shale	1950
Anhydrite	1980
Shale & lime	1990
Shale & Red Bed	2225
Lime & shale	3329
Lime	3480

No tops

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Harker

Subscribed and sworn to before me this 29th day of July, 1959.

Margie Cooper
Notary Public

My commission expires: 1-30-61.