



Locate well correctly on above Section Plat

Phillips County. Sec. 4 Twp. 1 Rge. 18W (X) (W)
 Location as "NE/CNW/SW" or footage from lines. C E/2 SE SW
 Lease Owner W. P. Simmons Oil Co.
 Lease Name Walker Well No. 1
 Office Address Box 54 Alma, Nebraska
 Character of Well (completed as Oil, Gas or Dry Hole) Oil - depleted
 Date well completed _____ 19____
 Application for plugging filed February 12, 19 63
 Application for plugging approved February 12, 19 63
 Plugging commenced _____ 19____
 Plugging completed February 2, 19 63
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3460' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" 154' circulated with cement - 1/2" 3460' with 75 sacks cement, Perf 3350'
Filled with sand to 3320', set 3 sacks cement with dump bailer, pulled 2000' 1/2" to 500', circulated hole with heavy mud through 1/2" at 500' (30 sacks Gel), displaced 20 sacks cement through 1/2" at 500' heavy mud to 165', displaced 20 sacks cement through 1/2" at 165' heavy mud to 40', set bridge and filled with cement to bottom of cellar.

Mudding and cementing by Sun Cementing Co.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 5 1963

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor R & D Casing Pulling
 Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF Redd, ss.
W. P. Simmons (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. P. Simmons
5830 N. Broadway Wichita Kans
 (Address)

SUBSCRIBED AND SWORN TO before me this 3 day of September, 19 63

My commission expires Nov. 16, 1965

Wilma A. Clark
 Notary Public.

15-147-19016-00-00

Lease: Walker 1 "B" c 1/2 SW SE
 Section 4-13-18W
 Phillips County, Kansas

Company: Simmons-Buick

Contractor: Buick Drilling Inc.

Commenced: September 29, 1961

Completed: October 6, 1961

Elevation: 2018 DF

Casing: 8 5/8" set @ 154 x/100 sacks
 4 1/2" set @ 3460

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 9 1963
 CONSERVATION DIVISION
 Wichita, Kansas

DEPTH	FORMATION
0 - 154	Shale
154 - 500	Shale
500 - 1380	Shale, sand and shells
1380 - 1595	Shale and shells
1595 - 1635	Sand
1635 - 1805	Sand and shale
1805 - 2150	Shale
2150 - 2220	Shale and lime
2220 - 2447	Shale and lime
2447 - 2575	Lime
2575 - 2725	Shale and lime
2725 - 2920	Lime and shale
2920 - 3063	Shale and lime
3063 - 3210	Lime
3210 - 3295	Lime
3295 - 3340	Lime
3340 - 3460	Lime
	Total Depth - Rotary

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 9 1963
 CONSERVATION DIVISION
 Wichita, Kansas

I, H. R. Buick, certify that the above log is true and correct according to the records of this office.

H. R. Buick - President