

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

15-147-20053-00-00
WELL PLUGGING RECORD

NORTH

Phillips County. Sec. 11 Twp. 1 Rge. 18 (E) (W) X
Location as "NE/CNW%SW%" or footage from lines NE SE NE
Lease Owner Don H. Peaker
Lease Name Adee Well No. #1
Office Address Box 1595 Pueblo, Colorado
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 7-21-70 19
Application for plugging approved 19
Plugging commenced 7-17-70 19
Plugging completed 7-23-70 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3630' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3630'	2625.57'
				8 5/8"	203'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3350'. Mixed and ran 4 sacks cement thru dump bailer.
Squeezed hole with 3 sacks hulls - followed with 15 sacks gel, followed with 70 sacks cement, followed with 2 sacks hulls. Released plug and displaced with 55 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of July, 1970

My commission expires October 1972
Sidney D. Miller
Notary Public.



KANSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

MAY 31 1969

COPY

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas

15-147-20053-00-00 DRILLERS LOG

No. 1 A. Adee

CASING RECORD:	COMPANY:	Don H. Peaker, etal	DESCRIPTION:
8 5/8" @ 203' w/165 ex. cement	CONTRACTOR:	Red Tiger Drilling Co.	NE SE NE 11-18-18W Phillips County Kansas
4 1/2" @ 3628' w/150 ex. cement	COMMENCED:	November 9, 1968	ELEVATION: 2097 KL
TOTAL DEPTH: 3630'	COMPLETED:	November 16, 1968	

Prod: oil

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	205	
Shale	205	720	
Shale & Sand	720	2040	
Shale & Lime	2040	3144	
Lime	3144	3630	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 20th day of November, 1968.

Jean Dallas
Notary Public

My Commission Expires:

5-23-70

