

4-031920

4-26

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,122 -00-00

C S2 NE /4 SEC. 15, 01 S, 18 W
3300 feet from S section line
1320 feet from E section line

Operator license# 5352

Lease Wolf well # 4

Operator: Baird Oil Company, Inc.

County Phillips

Address: Box 428
Logan, Kansas 67646

Well total depth 3496 feet ^{113.62}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 26 Month: April Year: 94

Plugging proposal received from: Jim Baird

Company: Barid Oil Company Phone:

Were: Order 200 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:30A.M., Day: 26, Month: April, Year: 94

Actual plugging report: 8 5/8" set @ 208' w/175 sxs. cwc. 5 1/2" set @ 3494' w/170 sxs. Prod. perfs. 3321' - 3380'. Critical area, control shots at 1690' and 1225'. P.B.T.D. 3475'. Squeezed 8 5/8" w/25 sxs. cement blend w/200# hulls. Squeezed 5 1/2" w/25 sxs. cement blend with 200# hulls. Followed by 12 sxs. gel, 150 sxs. cement blend w/200# hulls to Max. P.S.I. 400#. Close in P.S.I. 300#. Plug complete.

Remarks: Anhy. 1686' - 1693'.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO RECEIVED
Plugged through TUBING , CASING . Elevation: 2058 STATE CORPORATION COMMISSION

I did did not [] observe the plugging. Carl Goodrow APR 29 1994

INVOICED
DATE MAY 03 1994
INV. NO. 40372

HTD (agent) CONSERVATION DIVISION
Form CP-2/3 Wichita, Kansas