

4-041494

8-17

15-147-20083-00-01

C-17,599

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 12-11-1969

C W2 NE /4 SEC. 15, 01 S, 18 W
3960 feet from S section line
1980 feet from E section line

Operator license# 5352

Lease Wolf well # 2

Operator: Baird Oil, Inc.

County Phillips

Address: Box 428
Logan, Kansas 67646

Well total depth 3420 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 210 feet
w/150 sx.

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:30A.M. Day: 17 Month: August Year: 93

Plugging proposal received from: Jim Baird

Company: Baird Oil, Inc. Phone:

Were: 4 1/2" casing set @ 3449' w/135 sx. cement. Perf. @ 3286' -
3403'. Anhy. @ 1665'. Dakota @ 1125'. W.L.M. 3300'.
Ordered 200 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:30P.M., Day: 17, Month: August, Year: 93

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 25 sx. cement w/200# hulls and 8 sx. gel. and 125 sx. cement w/200# hulls. Max. 700#. S.I. 400#. Perf. base of S.P. @ 180'. Hooked-up to 4 1/2" casing. Pumped in additional 40 sx. cement w/100# hulls. Circulated cement to surface.

Remarks: Top of fluid: 2000'
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO
Plugged through TUBING , CASING X. Elevation: GL

I did [did not] observe the plugging.

Dennis L. Hamel AUG 20 1993

DATE AUG 30 1993

(agent) CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3

INV. NO. 38496

111.15

RECEIVED STATE CORPORATION COMMISSION