

4-032073

15-147-20028-00-01  
7-19-95

E-17,599-0002

API Number: 15- - 1968

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

C W2 SE /4 SEC. 15, 01 S, 18 W  
1320 feet from S section line  
1980 feet from E section line

Operator license# 5352

Lease: O'Neil Well # 2

Operator: Baird Oil Company, Inc.

County: Phillips 111.15

Address: P.O. Box 428  
Logan, Kansas 67646

Well total depth 3420 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 3/8 Inch @ 221 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 19 Month: July Year: 1995

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 01 1995

CONSERVATION DIVISION  
WICHITA KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 9:30 A.M., Day: 19, Month: July, Year: 1995

Actual plugging report: 8 5/8" set at 221' with 160 sxs. 4 1/2" set at 3419' with 200 sxs. P.B.T.D 3383'. Prod perms 3320' - 3363'. Critical area control shots at 1125' and 1680'. Squeezed 4 1/2" with 150 sxs cement blend with 300# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 400#. Test 8 5/8" to 1000# would not take cement. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

DATE 9-6-95

INV. NO. 43403