

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.  
Wichita, KS 67202

API Number 15-47-20180-00-00

Operator's Full Name BAIRD OIL COMPANY, INC.

Complete Address BOX 7 - LOGAN, KANS. 67646

Lease Name ULLOLF Well No. #6

Location C-NE Sec. 15 Twp. 1<sup>S</sup> Rge. 18<sup>W</sup> (East) (West)

County PHILLIPS Total Depth 3490<sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor MELSO CASING PULLING

Address BOX 176 CHASE, KANS License No. 683

Operation Completed: Hour: 11:30<sup>AM</sup> Day: 4<sup>TH</sup> Month: JUNE Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" 201<sup>FE</sup> CUC<sup>W</sup>/150<sup>ST</sup> ENT. -> 4 1/2" SET @ 3489<sup>FE</sup>  
PLUG. BACK T.D. 3455<sup>FE</sup> -> PERF'S TOP. 3292<sup>FE</sup>  
SET CAST IRON PLUG. @ 3200<sup>FE</sup> (PETRO-LOG.)  
SHOT PIPE 3 TIMES - RECOVERED 1973<sup>FE</sup> OF 4 1/2"  
PUMPED IN 8 5/8" WITH PUMP TRUCK.  
ORDERED 140<sup>ST</sup> 50/50 PREMIX 6% GEL -> 28<sup>ST</sup> GEL -> 4<sup>ST</sup> HULL'S + 8 5/8" PLUG.  
PUT IN -> 4<sup>ST</sup> HULL'S - 20<sup>ST</sup> GEL - 70<sup>ST</sup> ENT. -> 8<sup>ST</sup> GEL.  
RELEASED PLUG. AND 70<sup>ST</sup> ENT. MAX. PRESSURE - 200<sup>PSI</sup>

CEMENTED BY ALLIED CNT.

RECEIVED

I hereby certify STATE CORPORATION COMMISSION was plugged as herein stated.

INVOICED

JUN - 5 1981

Signed: Marvin Schmidt  
Conservation Division Agent

DATE 7-21-81

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 5891-W