

15-147-20005-0000^P

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

OCT 7 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leland R. Baird

Complete Address Logan, Kansas 67646

Lease Name Wayne O' Neil Well No. 1

Location C SW SW Sec. 15 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3567'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 1:30 P Day 3 Month 8/0 Year 1975

The above well was plugged as follows:

Total Depth 3567' 8 5/8 csg set 200' cwc 150 sk.

4 1/2 csg set 3566' cw 125 sk cem.

4 1/2 csg PFS (3519-3404)

Set 4 1/2 wood plug 3200' -poured 10' sd -dumped 4 sk cmt W/dump bailer. (3150-3200)

Cutoff & recovered A/2400' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk 50-

50 poz 2% -15 sk gel & water -released plug & 50 sk 50-50 poz cem 2% by "Allied".

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-8-75

Signed: Geo Massey
Well Plugging Supervisor

INV. NO. 2016-W