

API NUMBER 15-147-20105-00-00

LEASE NAME Oneil A

WELL NUMBER A-3

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 15 TWP. 1 RGE. 18 (E) or (W)

COUNTY Phillips

Date Well Completed 9-26-70

Plugging Commenced 7-19-95

Plugging Completed 7-19-95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Baird Oil Co. Inc

ADDRESS Box 428 Logan KS 67646

PHONE#(913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-21-95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation KC Depth to Top 3324 Bottom 3380 T.D. 3487

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>KC</u>	<u>oil + wtr</u>	<u>3324</u>	<u>3380</u>	<u>4 1/2</u>	<u>3519</u>	<u>None</u>
		<u>Surface</u>	<u>208</u>	<u>8 3/8</u>	<u>208</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

The casing was perforated at 1700 and 1125. Then 200 sxs of 60/40 Pozmix cement was pumped down 4 1/2 casing with 450# of hulls with a mix press of 400# PSI; shut-in pressure was 100#. The backside was plugged with 75 sx cement with 50# of hulls. Max pressure 400# and shut-in at 120#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. \_\_\_\_\_

Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

Jim R. Baird (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428 Logan KS 67646

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 95



Marilyn J. Whitsitt  
 Notary Public

My Commission Expires: 2-9-98