

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-20028-00-01

API NUMBER None

LEASE NAME Oneil

WELL NUMBER #2

1320 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 15 TWP. 1 RGE. 18 (E) or (W)

COUNTY Phillips

Date Well Completed 1-14-68

Plugging Commenced 7-19-95

Plugging Completed 7-19-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Baird Oil Co. Inc

ADDRESS Box 428 Logan, KS 67646

PHONE# (913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-21-95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? -

Producing Formation KC Depth to Top 3320 Bottom 3363 T.D. 3420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>KC</u>	<u>oil and wtr</u>	<u>3320</u>	<u>3363</u>	<u>4 1/2</u>	<u>3419</u>	<u>None</u>
		<u>surface</u>	<u>221</u>	<u>8 5/8</u>	<u>221</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 150 sx of 60/40 Pozmix cement with 300# of Halls down the 4 1/2 casing at a pressure of 1000#. Shut in at 400#. Rested 8 5/8 to 1600# and it held. Note: prior to cementing casing was perforated at 1680 and 1125.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. _____

Address Russell, KS


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF _____ COUNTY OF _____, ss.

Tim R. Baird (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tim R. Baird

(Address) Box 428 Logan, KS 67646



WITNESSED AND SWORN TO before me this 19th day of July, 19 95

Marion J. White
 Notary Public

My Commission Expires: 2-9-98