

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-147-20180-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Phillips SEC. 15 TWP. 1S RGE. 18W E/W
 Location as in quarters or footage from lines:
C - NE/4

Locate Well
 correctly on above
 Section Platt.

Lease Owner Baird Oil Co., Inc.
 Lease Name Wolf #6 Well No. _____
 Office Address Box 7, Logan, Ks. 67646
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 6/1/81
 Plugging completed 6/4/81
 Reason for abandonment of well or producing formation _____

RECEIVED
 STATE CORPORATION COMMISSION
 JUN - 8 1981

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes Wichita, Kansas

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom _____ T.D. 3490'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	201	None
				4 1/2"	3489	1975'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved onto location. Had to have pumping unit moved out and electric fence taken down. Set rig and rack in. Water was flowing out of surface and oil string - set cast iron plug at 3200'. Shot casing at 2369, 2173 and 1973. Pulled total of 62 joints. Had 8-5/8" collar welded on. Plugged well with 140 sacks 50/50 pos 6% gel, 28 sacks gel and 4 sacks hulls, and 8-5/8" plug. Plugging complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 81

My Commission expires:



Joan Kelso
 Notary Public.