

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Baird Oil Co. Inc

ADDRESS Box 428 Logan, KS 67646

PHONE#(913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-20-94 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Kansas City Depth to Top 3293 Bottom 3352 T.D. 3448

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Kansas City</u>	<u>water</u>	<u>3293</u>	<u>3352</u>	<u>5 1/2</u>	<u>3480</u>	<u>None</u>
Water	water			<u>8 5/8</u>	<u>217</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 25 sxs cement with 100# of Hulls down 8 5/8" max pressure 100# and 100# Initial Shut in pressure. Then pumped 25 sxs cement w/ 200# of Hulls down 5 1/2" followed by 12 sxs of gel followed by 150 sxs of cement w/ 200# of Hulls. All cement was 60/40 Coz. w/ 10% Gel and 1/4" Flowseal.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. _____

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co. Inc

STATE OF Kansas COUNTY OF Phillips, ss.

Jim R. Baird

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428 Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 28th day of April, 19 94



My Commission Expires: 2-9-98

Marilyn J. Allen
 Notary Public

