

State Corporation Commission
 Conservation Division
 Wichita State Office Bldg.
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-147-20, 162-000

LEASE NAME Oneil E

WELL NUMBER E-1

660' Ft. from S Section Line

3300' Ft. from E Section Line

SEC. 15 TWP. 15 RGE. 18 (E) or (W)

COUNTY Phillips

Date Well Completed 7/1/73

Plugging Commenced 6/18/98

Plugging Completed 6/18/98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Baird Oil Co. Inc.

ADDRESS Box 428 Logan, KS 67646

PHONE# (785) 689-7456 OPERATORS LICENSE NO. 83527

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/19/98

by Carl Goodcrow

(KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Lansing/KC Depth to Top 3285 Bottom 3503 T.D. 3515

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
unconsolidate	sand + shale	Surface	140	8 5/8	231	none
Lansing KC	shale + limestone	3285	3503	4 1/2	3497	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Pumped 25 sacks of cement (60-40 portmix with 10% Gel) down 8 5/8 and shut in with 100 PSI. Then pumped 175 sacks of cement (A/A) with 500# of Halls down the 4 1/2 casing. Filled the casing to the surface and shut-in.

Name of Plugging Contractor Allied Cementing License No. NA

Address P.O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co. Inc


STATE OF Kansas COUNTY OF Phillips, ss.

Jim R. Baird (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jim R Baird

(Address) Box 428 Logan, KS 67646



TO before me this 18th day of June, 19 98

Robert B. Hartman
 Notary Public

My Commission Expires: 3/29/99

USE ONLY ONE SIDE OF EACH FORM