

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-20070-00

API NUMBER None

LEASE NAME O'Neill A

WELL NUMBER A#2

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 15 TWP. 1S RGE. 18 (E) or (W)

COUNTY Phillips

Date Well Completed 5-2-69

Plugging Commenced 1-21-94

Plugging Completed 1-21-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Baird Oil Co., Inc.

ADDRESS Box 428 Logan, KS 67646

PHONE#(913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-17-94 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? was filed with CP-1 form

Producing Formation Kansas City Depth to Top 3307 Bottom not reached T.D. 3483

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation surface	Content	From surface	To	Size	Put in	Pulled out
Kansas City	sndy loam & shale	surface	220	8 5/8	220	none
	lime & shale	3307	3483	4 1/2	3485	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. squeezed 8 5/8 casing with 50 sks cement w/100# of hulls; max pressure 100#. Squeezed 4 1/2 casing with 25 sks cement w/100# of hulls; 12 sks of gel and 100 sks cement with 100# of hulls; max pressure 1000#. shut-in pressure 300#.

Note: prior to plugging the casing was perforated at 1200' and 1705'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. _____

Address P.O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co., Inc.

STATE OF Kansas COUNTY OF Phillips

Jim R. Baird

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird
Jim R. Baird, Exec. Vice-President

(Address) Box 428 Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 4th day of February, 19 94



Marilyn J. Allen
 Notary Public

My Commission Expires: 2-9-98