

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-147-20083-0001

API NUMBER Docket #C-17,599

LEASE NAME Wolf

WELL NUMBER #2

3960 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 15 TWP. 1 RGE. 18 ~~XX~~or(W)

COUNTY Phillips

Date Well Completed 12-18-1969

Plugging Commenced 8-17-1993

Plugging Completed 8-17-1993

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Baird Oil Co., Inc.

ADDRESS Box 428, Logan, KS., 67646

PHONE#(913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-17-1993 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation K.C. Depth to Top 3252 Bottom unknown T.D. 3450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand & loam	water	0	210	8-5/8	210	none
K.C.	oil & water	0	3449	4 1/2	3449	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. mixed 100# hulls followed by 25 sks. cement (60-40pox w/10% gel & 1/4# flocel) then 100# hulls followed by 8 sks. gel & 110 sks. cement A/A & 300# of hulls & displaced down the 4 1/2 csg. to 200'. Max. press. 700#, then perforated at 180' & mixed 40 sks. cement & circ. down 4 1/2 & to surface between 8-5/8 & 4 1/2  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. N/A

Address Plainville, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co., Inc.

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Jim R. Baird (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428, Logan, KS., 67646

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 93

Marilyn J. Allen  
 Notary Public

My Commission Expires: 2-9-94



RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 23 1993