

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

13-147-00685-00-00

FILE NO. _____

LOCATION SE SW SE

SEC. 21 TWP. 1 RGE. 18 *w*

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. G-2 Lease Jackson

Operator B & R Drg Co Address Russell, Kans

Field _____ County Phillips

Total Depth 3485 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 201' circulated with cement - 5 1/2" at 3484' with
120 sax cement behind - Lane Wells plugs to 3475' - perforations
3571'.

Filled with chat to 3560', set 4 sax cement with dump bailer,
pulled 2000' 5 1/2", filled hole with mud to 200', set rock bridge
and 10 sax cement, filled with mud to 35', set rock and 10 sax
cement to bottom cellar.

PLUGGING
FILE SEC 21 T 1 R 18 W
BOOK PAGE 133 LINE 36

John Perry
District Conservation Agent
Date 12-23-61
STATE CORPORATION COMMISSION

RECEIVED
DEC 26 1951
CONSERVATION DIVISION
Wichita, Kansas