

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-00686-00-00

FILE NO. \_\_\_\_\_

LOCATION SE <sup>NW</sup> SW SE

SEC. 21 TWP. 1 RGE. 18 *w*

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. C-<sup>3</sup>~~2~~ Lease Jackson

Operator B & R Drg Co Address Russell, Kans

Field \_\_\_\_\_ County Phillips

Total Depth ~~3485~~<sup>3500</sup> Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 201' circulated with cement - 5 1/2" at 3484' with 150 sax  
cement behind - cement to 3475' - top perforations at 3371'.  
Filled with chat to 3360', set 4 sax cement with dump bailer,  
pulled 2500' 5 1/2", filled hole with mud to 200', set rock and  
15 sax cement, mud to 35', set rock and 10 sax cement to bottom  
cellar.

STATION

FEB 9 X 1952

CONSERVATION DIVISION  
Wichita, Kansas

*J. Edgar Kelly*  
District Conservation Agent

Date 2-5-52

**PLUGGING**  
FILE SEC 21 TWP. 1 RGE. 18 *w*  
BOOK PAGE 142 LINE 25