

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-19005-00-00 ~~00~~ ^{X-01}
Spot: CSWSW Sec/Twnshp/Rge: 20-1S-18W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: SCHLUNTZ Well Number: 4
County: PHILLIPS Total Vertical Depth: 3589 feet

Operator License No.: 31070 Conductor Pipe: Size feet: 116.64
Op Name: EAGLE RIVER ENERGY CORPORATION Surface Casing: Size 8.5 feet: 216 160 sx
Address: 7060 S. YALE #609 Production: Size 4.5 feet: 3619 200 sx
TULSA, OK 74136 Liner: Size feet:

Well Type: EOR UIC Docket No: E06746.13 Date/Time to Plug: 03/11/2002 8:00 AM
Plug Co. License No.: 31070 Plug Co. Name: EAGLE RIVER ENERGY CORPORATION
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/11/2002 10:40 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Squeezed 8 5/8" S.P. - annulus with 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.
Squeezed 4 1/2" casing with 175 sxs cement with 500# hulls mixed in cement.
Max. P.S.I. 1000#. S.I.P. 700#.

RECEIVED
MAR 29 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE March 29-02

INV. NO. 2002061584

MAR 27 2002

LIVINGSTON OIL CO #4 SCHLUNTZ 20-1-18W
C SW SW

Contr. MAST DRLG PHILLIPS County

E 2180 RB Comm. Comp. 3-31-61 IP 20 BOPD

LOG Tops	Depth	Datum	Casing
			8" 215
HEEB	3326	-1146	5" 3619
TOR	3352	-1172	
LANS	3368	-1188	CO 3590: ABR JET 3520: NS: ACID 500: JET/3608: ACID 500: JET/ 3460: ACID 500: 1/2 BOPH & 3/4 BW JET/3423: ACID 1000: 2 BOPH & 2 BWPH/12 HRS: JET/3407: ACID 500: CO 3590
B/KC	3590	-1410	
TD	3620	-1440	HUFFSTUTTER POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS
