

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00932-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 21-1S-18W  
2310 feet from N Section Line, 1650 feet from W Section Line  
Lease/Unit Name: JACKSON - G Well Number: 2  
County: PHILLIPS Total Vertical Depth: 3490 feet

Operator License No.: 31070 Conductor Pipe: Size \_\_\_\_\_ feet:  
Op Name: EAGLE RIVER ENERGY CORPORATION Surface Casing: Size 8.62 feet: 208 175 SX CMT  
Address: 7060 S. YALE #609 Production: Size 5.5 feet: 3489 175 SX CMT 3113.43  
TULSA, OK 74136 Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2001 10:00 AM

Plug Co. License No.: 31154 Plug Co. Name: RICE PRODUCTION COMPANY  
Proposal Rcvd. from: GEORGE RICE Company: RICE PRODUCTION COMPANY Phone: (316) 793-2645

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel with 1/4# Flo-seal and 600# hulls.  
Perfs 3393' - 3397'; 3411' - 3415'; 3436' - 3440'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/13/2001 12:45 PM KCC Agent: PAT STAAB


**Actual Plugging Report:**

Fisher Well Service RIH with tubing to 2600' - pumped 100 sxs 60/40 pozmix with 200# hulls.  
Pulled tubing to 1700' - spotted 75 sxs 60/40 pozmix with 200# hulls.  
Pulled tubing to 900' - pumped 80 sxs with 200# hulls until cement circulated to surface.  
Tied onto backside - pumped 50 sxs 60/40 pozmix with Max. P.S.I. 300#. S.I.P. 100#.  
Tied onto 8 5/8" casing - pumped PTOH with 20 sxs 60/40 pozmix with Max. P.S.I. 400#. S.I.P. 200#.

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
JUN 15 2001  
CONSERVATION DIVISION

**INVOICED**  
DATE 6-15-01  
WV. NO. 2001061952

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: TBG

District: 04 Signed   
(TECHNICIAN)

JUN 14 2001

LIVINGSTON OIL CO #2 JACKSON, 'G' 21-1-18W  
NW NE SW

Contr. EARL F WAKEFIELD PHILLIPS County

E2158RB Comm. 10-8-57 Comp. 12-20-57 IP 24 BOPD

Tops	Depth	Datum
ANK	1742	+416
TOP	3096	-938
HEEB	3307	-1119
LATAN	3311	-1186
LANS	3359	-1201
TD	3491	-1332

Casing  
8" 197  
5" 3439  
DST 3375-3400, 15' OCM  
DST 3398-3418, 16' OCM  
DST 3418-40, 12' OCM  
DST 3439-59, 14' MUD  
PERF 3436-40, 3411-15, 3393-97  
HUFFSTUTTER POOL

+	+	+
+	+	+

DAKOTA - 953 - 1253  
ANK - 1742 - 1760

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS