

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00935-00-00
Spot: CNWSWNW Sec/Twnshp/Rge: 21-1S-18W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: THOMAS - A Well Number: 1
County: PHILLIPS Total Vertical Depth: 3522 feet

Operator License No.: 31070 Conductor Pipe: Size feet: \$ 114.47
Op Name: EAGLE RIVER ENERGY CORPORATION Surface Casing: Size 10.75 feet: 189 175 SX CMT
Address: 7060 S. YALE #609 Production: Size 7 feet: 3520 175 SX CMT
TULSA, OK 74136 Liner: Size feet:

Well Type: WSW UIC Docket No: Date/Time to Plug: 03/07/2002 9:30 AM

Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC

Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Ordered out 425 sxs 60/40 pozmix - 10% gel - 700# hulls.
PBTB 3000'.
Dakota Water Supply Well.

Plugging Proposal Received By: JAY PFEIFER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/07/2002 11:30 AM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2000' and spotted 120 sxs.
Pulled up to 1000' and circulated up 7" with 70 sxs.
POOH. Swedged on 7" and circulated up 10" with 90 sxs and 300# hulls.
Shut in and pumped to pressure with 135 sxs and 400# hulls.
S.I.P. 200#.

RECEIVED
MAR 11 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE Mar 12-02

INV. NO. 2002061515

Form CP-2/3

MAR 08 2002

LIVINGSTON OIL CO #1 THOMAS 'A' 21-1-18W
NW SW NW

Contr. EARL F WAKEFIELD PHILLIPS County

E2169RB Comm. 9-15-57 Comp. 12-20-57 IP 79 BOPD

Tops	Depth	Datum	Casing
			10" 189
TOP	3113	-944	7" 3520
HEEB	3324	-1155	DST 3392-3414, 15' VH OCM, 60'
IATAN	3356	-1187	SL OCM
LANS	3374	-1205	DST 3412-34, 60' OCM
			DST 3433-55, 45' VH OCM
			DST 3454-74, 20' MUD
			PERF 3444-48, 3424-28, 3407-
			HUFFSTUTTER POOL
TD	3522	-1352	11

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS
