

4-041655

1-25  
15-147-30180-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 6-51  
NW NE NE /4 SEC. 21, 01 S, 18 W  
330 4950 feet from ~~W~~ section line  
990 feet from E section line

Operator license# 31070 Lease Stevens well # 1

Operator: Eagle River Energy Corporation County Phillips

Address: 7060 S. Yale Well total depth 3480 feet <sup>113.10</sup>  
Suite #609 Conductor Pipe: 0 inch @ 0 feet  
Tulsa, OK 74136 Surface pipe 10 3/4 Inch @ 212 feet  
w/125 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 25 Month: January Year: 95

Plugging proposal received from: Jerry Rice

Company: Eagle River Energy Corporation Phone:           

Were: 5 1/2" casing set at 3474' w/150 sxs. cement. Perfs. at  
3330' - 3447'. Anhy. @ 1840' - Dakota @ 1200' - W.L.M. @ 3400' -  
T.O.F. @ 3100'. Perf. anhy. @ 1840' - Perf. Dakota @ 1200'.  
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls  
and 8 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 2:00P.M., Day: 25, Month: January, Year: 95

Actual plugging report: R. U. cementers to pump down 5 1/2" casing with  
25 sxs. cement with 200# hulls, followed with 8 sxs. gel, followed with  
150 sxs. cement and 200# hulls. Max. P.S.I. 300#. S.I.P. 200#.  
Pumped down 10 3/4" S.P. with 50 sxs. cement and 100# hulls mixed in  
cement. Max. P.S.I. 400#. S.I.P. 200#.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 07 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks:  
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:            GL

I did X observe the plugging. Dennis L. Hamel

DATE 2-8-95  
INV. NO. 42186

(agent)  
Form CP-2/3

HO