

6 010558

10-8-8715-147-19035-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1957  
NE, SEC. 21, T 1 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4807

feet from S section line  
feet from E section line

Operator: G. K. M. Inc.  
Name & Address: Box 520  
Great Bend, Kansas

Lease Name Jackson Well # A-1 H-1  
County Phillips 111.38

Well Total Depth 3427 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 182

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor G. K. M. Inc. License Number 4807

Address Great Bend, Kansas

Company to plug at: Hour: Day: 8 Month: Oct. Year: 19 87

Plugging proposal received from Jerry Rice

(company name) G. K. M. Inc. (phone)

were: Perf anhydrite and base of Dakota. Order 250 sks cement. 65/35 Pozmix 10% Gel  
2% Econolite 500# Hulls. 5 1/2 at 3427' Perf 3330' - 3422'

Elevation 2123' Anhydrite 1715'

Dakato 1250'

873'

Plugging Proposal Received by D. F. B. (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: Day: 8 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing 50 sks cement. Then 100 sks  
cement w/300# Hulls. Max pump pressure 400#. Closed w/200#. Pumped down 8 5/8

100 sks cement w/200# Hulls. Max pump pressure 200#. Closed w/100#.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: B. J. Titan Cementing Co.

(If additional description is necessary, use BACK of this form.)

(If ~~XXXXXX~~ observe this plugging.

INVOICED

DATE 10-20-87

INV. NO. 18569

10-08 DEC 03 1987

Signed Dale F. Balthazor (TECHNICIAN)

Dale F. Balthazor