

10-8-87 15-147-19031-00-01

To: 6 010557
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1 - 1963
NW, SEC. 17, T. 1 S, R. 18 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4807

Lease Name Lutieharm Well # 4

Operator: G. K. M. Inc.

County Phillips 115.21

Name & Address Box 520

Well Total Depth 3545 feet

Great Bend, Kansas 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor G. K. M. Inc. License Number 4807

Address Great Bend, Kansas

Company to plug at: Hour: _____ Day: 8 Month: October Year: 19 87

Plugging proposal received from Jerry Rice

(company name) G. K. M. Inc. (phone) _____

were: Perf. anhydrite and base of dakota. Order 250 sks cement 65/35 Pozmix 10% Gel
2% Econolite 500# Hulls. 4 1/2 at 3542'. Perf 3291' - 3445'.

Elev 2083'

Dakota 1200' Anhydrite 1677'

883'

Plugging Proposal Received by D. F. B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: _____ Day: 8 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing 50 sks cement. Then 75 sks cement w/250#
Hulls. Max pump pressure 800# closed w/400#. Pumped down 8 5/8" 125 sks cement w/250# Hulls.
Max pump press 500# Closed w/200#.

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: B. J. Titan Cementing Co.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 10-20-87

Signed Dale F. Balthazor
(TECHNICIAN)

Dale F. Balthazor

INV. NO. 12566

DEC 03 1987

FORM CP-2/3
Rev. 01-84 LR

10-08