

4-041499

7-12

15-147-30022-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - N/A

E2 W2 W2 /4 SEC. 20, 01 S, 18 W
2640 feet from S section line
4290 feet from E section line

Operator license# 31070 Lease Schluntz well # 6

Operator: Eagle River Energy Corporation County Phillips 116.51

Address: 7060 S. Yale Well total depth 3585 feet
Suite 609 Conductor Pipe: 0 inch @ 0 feet
Tulsa, Oklahoma 74136 Surface pipe 8 5/8 Inch @ 213 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 12 Month: July Year: 93

Plugging proposal received from: Jerry Rice

Company: Eagle River Energy Corporation Phone:

Were: 4 1/2" casing set @ 3585' w/150 sxs. cement. Perfs. @ 3376' - 3440'. Anhy. @ 1740' - Dakota @ 1250' - W.L.M. 3400' - T.O.F. @ 600'. Order 250 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

No Salt Section

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:30A.M., Day: 12, Month: July, Year: 93

Actual plugging report: R.I.H. with tubing to 1700'. Spot 160 sxs. 60/40 pozmix - 10% gel with 450# hulls. P.O.O.H. with tubing and squeeze 25 sxs. cement down casing. Max. 300#. S.I. 100#. Hooked-up to 8 5/8" S.P. Squeezed 35 sxs. cement down annulus with 100# hulls in cement. Max. 400#. S.I. 200#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X / did not observe the plugging.

Dennis L. Hamel SEP 13 1993

INVOICED
SEP 14 1993

DATE
SER. NO. 38629

(agent) CONSERVATION DIVISION
Form CP-2/3 Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISS