

6 010607

4-8-88 ^{not on computer} 15-147-00144-00-60 ^{do chert # ?}
API NUMBER 15- Old Well

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NW SEC. 20, T 1, R 18 (WYE)
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4807

Lease Name Schluntz Well # 1

Operator: G.K.M.
Name & Address Box 520
Great Bend, Ke.

County Phillips 123.99

RECEIVED
STATE CORPORATION COMMISSION
Aug 4, 1988
Wichita, Kansas

Well Total Depth 3815' PB 3468 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 185

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well ² X D&A

Other well as hereinafter indicated _____

Plugging Contractor G.K.M. License Number 4807

Address Same

Company to plug at: Hour: AM Day: 8 Month: April, Year: 19 88

Plugging proposal received from Jerry Rice

(company name) G.K.M. (phone) _____

were: Order 50 sx common cmt w/ 3/4 sx flocele, 325 sx cem 60/40 pozmix, 8% gel, 200# hulls.

5 1/2" @ 3490', Perf @ 3356-3403'. Perf Dakota @ 1212 Perf Anhy. @ 1710'

Elevation 2112', Anhydrite 1695'.

Plugging Proposal Received by D.F.B
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15PM Day: 8 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Pumped 50 sx common cmt down 5 1/2" w/3/4 sx flocele. Then 225 sx
cmt 60/40 pozmix, 8% gel, w/100# hulls in last 100 sx. Max pressure 450#. Close w/ 300#.
Pumped down 8 5/8", 100 sx cmt. 60/40 pozmix. Max pressure 350#. Closed w/ 150#.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to contractor observe this plugging.)

DATE 8-5-88

Signed Dale F. Balthazor
(TECHNICIAN)

INV. NO. 21772

Dale F. Balthazor