

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00929-00-00-01
Spot: SWSESW Sec/Twnshp/Rge: 21-1S-18W
330 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: JACKSON F Well Number: 1
County: PHILLIPS Total Vertical Depth: 3410 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATION
Address: 7060 S. YALE #609
TULSA, OK 74136

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 202 140 SX CMT
Production: Size 5.5 feet: 3422 75 SX CMT 110.83
Liner: Size feet:

Well Type: EOR UIC Docket No: E06746.6 Date/Time to Plug: 01/11/2001 9:00 AM

Plug Co. License No.: 31070 Plug Co. Name: EAGLE RIVER ENERGY CORPORATION

Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (918) 494-8928

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
T.O.F. 485' est.

Plugging Proposal Received By: DENNIS HAMEL
Date/Time Plugging Completed: 01/11/2001 12:45 PM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 1800'.
Spotted 150 sxs cement with 400# hulls in cement - cement circulated to surface.
Pulled tubing and squeezed casing with 25 sxs cement.
Max. P.S.I. 300#.
RU Cementers to 8 5/8" S.P. Squeezed 50 sxs cement with 100# hulls.
Max. P.S.I. 200#. S.I.P. 100#.
Job complete.

INVOICED
DATE 03-08-2001
INV. NO. 2001061401

Remarks: ALLIED CEMENTING COMPANY - RUSSELL, KANSAS

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 2001

FEB 08 2001

PRUGH PRODUCTION

#1 JACKSON

21-1-18W
SW SE SW

Contr. SAUVAGE & DUNN

PHILLIPS County

E 2127RB

Comm.

Comp.

12-2-55

IP


57 BOPD

Tops	Depth	Datum
HEEB	3275	-1148
LANS	3305	-1178
B/KC	3535	-1408
ARB	3705	-1578
TD	3710	-1583

Casing
5" 3430

PERF 3385-90: NS: ACID
 500: 1/2 BOPH: PB 3380:
 PERF 3365-70: ACID 1250
 1 BOPH: PB: PERF 3345-55
 ACID 1250: 2 1/2 BOPH: 300
 3380: 4 BOPH

HUFFSTUTTER POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS