

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6029 EXPIRATION DATE

OPERATOR Ladd Petroleum Corporation API NO. 15-147-20,394 - 00-00

ADDRESS 830 Denver Club Bldg COUNTY Phillips
Denver Colorado 80202 FIELD N. Huffstutter

** CONTACT PERSON Bill Riley PROD. FORMATION LKC
PHONE 316-792-3571

PURCHASER NCRA LEASE Lutjeharm

ADDRESS Box 1167 WELL NO. 6
McPherson, Kansas 67460 WELL LOCATION App N 1/2-SE-SE

DRILLING Murfin Drlg Co. 1250 Ft. from S Line and
CONTRACTOR 617 Union Center Bldg. 750 Ft. from E Line of
ADDRESS Wichita, Kansas 67202 the SE 1/4 (Qtr.) SEC 17 TWP 1S RGE 18W.

PLUGGING NA CONTRACTOR ADDRESS

TOTAL DEPTH 3500 PBTD 3426
SPUD DATE 10-28-82 DATE COMPLETED 12-1-82
ELEV: GR 2088 DF KB 2093

DRILLED WITH (CABLE) ROTARY (AIR) TOOLS.
DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING
USED TO DISPOSE OF WATER FROM THIS LEASE (587130) (6746)

Amount of surface pipe set and cemented 252 DV Tool Used? Yes

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

WELL PLAT

(Office Use Only)

Grid table with 4 columns and 4 rows. Cell (3,2) contains '17'. Cell (4,4) contains a solid black circle.

KCC
KGS
SWD/REP
PLG.

A F F I D A V I T


William Riley, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

William V. Riley (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 20th day of January, 1983,

19



Howard D. Ewert (NOTARY PUBLIC)

MY COMMISSION EXPIRES: December 15, 1984

** The person who can be reached by phone regarding any questions concerning this information.

STATE RECEIVED
COMMISSION
JAN 21 1983
Wichita, Kansas

OPERATOR Ladd Petroleum Corporation LEASE Lutjeharm SEC. 17 TWP. 1 RGE. 18W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lime/Shale	- 767		Topeka	2860
Shale	-1141		Heebner	3234
Lime/Shale	-1170		Toronto	3263
Lime/Shale	-1189		LKC	3282

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Secks	Type and percent additives
Surface	12 1/4	8 5/8	24	259	Class A	190	3% CaCl 2% Gel
Oil String	7 7/8	4 1/2	10.5	3489	1: 60/40 Poz 2: Light	1: 250 2: 200	1: 2% Gel 2: Light

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval
			4		3348-52
TUBING RECORD			4		3318-3322
Size	Setting depth	Pecker set at	4		3331-35
2 3/8"		None	4		3358-62

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 Gal Acid	OA 3318-62

Date of first production 12-1-82	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil 39 bbls.	Gas 0 MCF
	Water % -	Gas-oil ratio 0 CFB
Disposition of gas (vented, used on lease or sold) Vented		Perforations