

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10503-00-01
Spot: NWNW Sec/Twnshp/Rge: 21-34S-43W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: INTERSTATE Well #: 30
County: MORTON Total Vertical Depth: 4265 feet

Operator License No.: 4549 CIBP Size: feet: 4080 WITH 2 SX CMT
Op Name: ANADARKO PETROLEUM CORPORATI COND Size: 12.5 feet: 97
Address: 1201 LAKE ROBBINS DRIVE PROD Size: 4.5 feet: 4230 WITH 500 SX CMT
THE WOODLANDS, TX 77380 SURF Size: 8.625 feet: 1143 WITH 750 SX CMT

\$138⁶¹

Well Type: EOR UIC Docket No: Date/Time to Plug: 02/11/2004 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4080' WITH 2 SX CMT. PLUG AT 1160' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2004 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4145'. CIBP SET @ 4080' WITH 2 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1160'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 400'. LOAD HOLE & PUMP 30 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4136	4230		

RECEIVED
MAR 03 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1222' OF 4 1/2" CASING.

Plugged through: CSG

District:



Signed

Jim Holland PART II

INVOICED
(TECHNICIAN)
DATE 3-3-04
INV. NO. 2004061247

Form CP-2