

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20615-00-00
Spot: N2SENE Sec/Twnshp/Rge: 8-16S-10W
1650 feet from N Section Line, 660 feet from E Section Line
Lease Name: HARBACEK Well #: 1
County: ELLSWORTH Total Vertical Depth: 3315 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

PROD Size: 4.5 feet: 3314 150 SX CMT
SURF Size: 8.625 feet: 277 170 SX CMT

#107 74

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2004 11:15 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
FEB 27 2004

WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: PARTIAL
Date/Time Plugging Completed: 02/23/2004 12:10 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3201' and put 4 sacks of cement on top. Cut off 4-1/2" casing @ 1430'. Pulled to 1000' and pumped 35 sacks of cement. Pulled casing to 650' and pumped 35 sacks of cement. Pulled casing to 325' and circulated cement to surface with 100 lbs cotton hulls.

Pumped 100 lbs cotton hulls at 1000' and 650'.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3279	3284		
3275	3279		

Remarks: ALLED TICKET #16969

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 3-3-04
INV. NO. 2004061246