

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03023-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 2-9S-19W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BARRY LKC UNIT Well #: 6-35
County: ROOKS Total Vertical Depth: 3473 feet

Operator License No.: 32754
Op Name: ELYSIUM ENERGY, L.L.C.
Address: 1625 BROADWAY, SU 2000
DENVER, CO 80202

PROD Size: 6 feet: 3466 w/300 sxs cmt
SURF Size: 10.75 feet: 238 w/200 sxs cmt

\$112⁸⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2004 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: ELYSIUM ENERGY, L.L.C. Phone: (785) 434-4638

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Arbuckle open hole squeezed 02-1968 w/50 sxs cement return at 3436'.
Lower LKC perms squeezed 03-1985 w/300 sxs cement return at 3160'.
Fluid level 1800'. PBTB 3160'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2004 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 280 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Hooked up to 10 3/4". Allied pumped 50 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3123	3150		Topeka Perfs

RECEIVED
MAR 03 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

3-3-04

INV. NO.

2004061249

Form CP-2/3

FEB 27 2004