


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



15-147-19030-00-00

WELL PLUGGING RECORD



Locate well correctly on above  
Section Flat

Phillips County, Sec. 17 Twp. 1 Rge. 18 (E) (W) X  
Location as "NE/CNW&SW&" or footage from lines Cof NE NW  
Lease Owner Leland Baird  
Lease Name L & G Well No. #1  
Office Address Logan, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 10-23-73 19  
Plugging completed 10-29-73 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3525' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3524'	2470.48'
				8 5/8"	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3270'. Mixed and ran 3 sacks cement thru dump bailer.  
Squeezed hole with 3 sacks hulls and 20 sacks gel. 2 sacks hulls, 70 sacks cement and 15 sacks gel. Released plug and displaced with 50 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1973  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364 Great Bend, Kansas (Address)

Subscribed and sworn to before me this 30 day of October, 1973

My commission expires 24 October 1976



Sidney D. Miller  
Notary Public.

B & B DRILLING, INC.  
720 Union Center  
Wichita, Kansas 67202

June 22, 1972

DRILLERS LOG

RECEIVED  
STATE COMMISSION COMMISSION

SEP 26 1973

REGISTRATION DIVISION  
STATE OF KANSAS

OPERATOR: Leland R. Baird  
CONTRACTOR: B & B Drilling, Inc.  
COMMENCED: June 13, 1972  
COMPLETED: June 20, 1972  
TOTAL DEPTH: 3525'

15-147-19030-00-00

Re: L & G #1  
C NE NW Section 17-1S-18W  
Phillips County, Kansas  
Set 228' 8 5/8" w/150 sx

0	228	Surface	
228	447	Shale	
447	1458	Shale & Sand	
1458	1693	Sand & Shale	
1693	1698	Anhydrite	
1698	1984	Shale	
1984	2540	Shale	
2550	2660	Shale & Lime	
2660	2880	Shale & Lime	
2880	3216	Lime	
3216	3328	Lime	
3328	3367	Lime	
3367	3446	Lime	
3446	3522	Lime	
3522	3525	Lime	
3525		Total Depth	Ran 4 1/2" Set @ 3524' w/35 sx

We certify the above and foregoing to be true and correct copy of the log on the #1 L & G, located in Phillips County, Kansas.

Bill Lohan President

Alma C. Neiser Notary Public

Subscribed and sworn to before me this 22nd day of June, 1972. My commission expires May 31, 1974