

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

19-147-20172-06-00
VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 30 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Leland R. Baird

Complete Address: Logan, Kansas

Lease Name: Imm Well No. 2

Location: NE SE Sec. 16 Twp. 1 Rge. (E)(W) 18

County: Phillips Total Depth 3577 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weber was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1280' and displace
70 sk cmt thru drill pipe. Heavy mud to 185' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent