

KANSAS

*12*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name LVO Corporation 15-147-01023-06-00

Complete Address Box 814 Great Bend, Kansas 67530

Lease Name Scott Well No. 1

Location SE <sup>SW</sup> SE Sec. 16 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3473'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box <sup>3</sup> 364 Great Bend, Kansas License No. 399'

Operation Completed: Hour 4 P Day 9 Month 12 Year 1970

The above well was plugged as follows:

Total Depth 3473' 10 3/4" csg set at 203' cwc 125' sk.

5 1/2" csg set at 3472' cw 150 sk cmt.

5 1/2" csg PBTD 3438' with perf. (3317-3450)

Filled 5 1/2" csg W/sd (3250-3438) Dumped 5 sk cmt W/dump bailer. (3210-3250)

Cutoff and recovered 1390' of 5 1/2" csg.

Pumped down 10 3/4" csg with 20 sk gel W/5 sk hulls - 75 sk poz 6% - 10 sk gel -

released plug and pumped 75 sk poz 6%. Pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Messer  
Well Plugging Supervisor

DATE 12/11/70  
INV. NO. 3043-U