

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-19029-0000

FILE NO. \_\_\_\_\_

LOCATION SE SE SE

SEC. 16 TWP. 1 RGE. 18 *W*

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. D-1 Lease Imm

Operator B & R Drg Co Address Russell, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3446 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 194' circulated with cement - 5 1/2" at 3442' with 150  
sax cement behind, Baker plugs to 3394', perforations at  
3022'.

Chat to 3315', set 4 sax cement with dump bailer, pulled  
3600' 5 1/2", filled with mud to 194', set rock and 15 sax cement,  
filled with mud to 35', set rock and 10 sax cement to bottom  
cellar.

**PLUGGING**  
FILE SEC 16 T 1 R 18  
BOOK PAGE 13 LINE 44

*E. J. Kelly*  
District Conservation Agent  
Date 12-17-51  
DEC 21 1951  
CONSERVATION DIVISION  
Wichita, Kansas