

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 30 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Leland R. Baird 15-147-20172-00-00

Complete Address Logan, Kansas

Lease Name Imm Well No. 2

Location NE SE Sec. 16 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3577'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:30 P Day 26 Month 5 Year 1974

The above well was plugged as follows:

RTD 3577' 8 5/8 csg set at 203' cwc 135 sk. Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 1280' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. H. Massey
Well Plugging Supervisor

INVOICED

DATE 5/5/74

INV. NO. 9236-W