

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

15-147-20230-00-00
API Number 15 - - (of this well)

Operator's Full Name LADD PETROLEUM CORPORATION
Complete Address 830 DENVER CLUB BUILD - DENVER, COLORADO 80202
Lease Name SCOTT Well No. "A" #1
Location NW-NE Sec. 16 Twp. 1^S Rge. 18(E) (W) W
County PHILLIPS Total Depth 3581^{EE}
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____

Plugging Contractor GLENN'S CASING PULLING, INC.
Address BOX 413 ELLENWOOD, MISS. 67526 License No. 832
Operation Completed: Hour 2:30^{PM} Day 6th Month MAY Year 1980

The above well was plugged as follows:
8 5/8" 286^{EE} SD. CUL w/ 200ST CNT. - 5 1/2" SET AT 3578^{EE} w/ 175ST CNT.
PLUG. BACK. 3547^{EE} PERFS - 3351^{EE} 3530^{EE} -> 5 1/2" SQUEEZED ->
BOTTOM SANDED AND 5ST CNT TO 3300^{EE}
SHOT PIPE 2 TIMES RECOVERED 518^{EE}
ORDERED 135ST 50% PORNIX 6% GEL -> 17ST GEL -> 5ST HULLS + 8 5/8" PLUG.
PUT IN 3ST HULLS - 5ST GEL -> 65ST CNT. -> 12ST GEL - 3ST HULLS
AND 40ST CNT. - MAX PRESSURE - 200^{PSI}
CEMENTED BY ALIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

Signed: Morton Schmidt
Well Plugging Supervisor

INVOICED
DATE 5-7-80
INV. NO. 2117W

RECEIVED
MAY 11 1980
CONSERVATION DIVISION
Wichita, Kansas