

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1973  
CONSERVATION DIVISION  
Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-147-20157-00-00

Operator's Full Name Leland R. Baird ~~15-147-14030-00-00~~

Complete Address Logan, Kansas 67646

Lease Name Elton Lutjeharms Well No. 1

Location C. NE NW Sec. 17 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3525'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 11:30 A Day 29 Month 10 Year 1973

The above well was plugged as follows:

Total Depth 3525' 8 5/8 csg set at 228' cwc 150 sk.

4 1/2 csg set at 3534' cw 235 sk cmt.

PBTD 3330' with perf. 3286 & 3287.

Filled 4 1/2 csg W/sd (3270' - dumped 3 sk cmt W/dump bailer. (3235-3270)

Cutoff and recovered 2469' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls - 70 sk cmt - 15 sk

gel & water - released 8 5/8 plug & pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Massey  
Well Plugging Supervisor

INVOICED

DATE 11/2/73

INV. NO. 8108-W