

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

15-147-19040-00-00
API Number 15 - - N.A. (of this well)

Operator's Full Name SIERRA PETROLEUM COMPANY INC.
Complete Address P.O. BOX 247 - WICHITA, KANS. 67201
Lease Name SCHLUNTZ Well No. #7
Location C - SW/4 - SE/4 Sec. 19 Twp. 1^S Rge. 18 (E) (W) W
County PHILLIPS Total Depth 3620 FT
Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereafter indicated _____

Plugging Contractor CELSO CASING PULLING
Address BOX 176 CHASE, KANS. 67524 License No. 68
Operation Completed: Hour 2:50 Day 12th Month AUG. Year 1980

RECEIVED
STATE CORPORATION COMMISSION
1 AUG 14 1980
CONSERVATION DIVISION
Wichita, Kansas

The Above well was plugged as follows:

8 5/8" 218ST SP. CUC w/150ST QUICK SET -> 4 1/2" SET @ 2591 FT w/125ST CNT.
PERF'S 3425^{FT} TOP. - BOTTOM CAVED IN - COULD REACH ONLY 1000 FT
SHOT (1) RECOVERED 810 FT
ORDERED 140ST 50ST Pozmix 6% GEL - 18ST GEL - 5ST HULL'S -
PUMPED IN WITH PUMP TRUCK.
PUT IN 2ST HULL'S - 8ST GEL - 70ST CNT. - 10ST GEL - 2ST HULL'S
AND 70ST CNT. - MAX. PRESSURE 250^{PSI}
CEMENTED BY ALLIED CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8-14-80

INV. NO. 2865-W