

DISTRICT CONSERVATION AGENT'S REPORT

170

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-30188-00-00

FILE NO. _____

LOCATION SE NW NE

SEC. 19 TWP. 1 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Artz _____

Operator Lawrence & Meltzer Address Box 414 Great Bend, Kans

Field _____ County Phillips

Total Depth 3534 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 195' circulated with cement - 5 1/2" at 3534' with
200 sax cement behind - Lane Wells plugs to 3420', top perforations
at 3390'.

Filled with chat to 3380', set 4 sax cement with dump bailer,
pulled 2300' 5 1/2", filled hole with mud to 195', set rock
and 15 sax cement, filled with mud to 35', set rock and 10 sax
cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1951
CONSERVATION DIVISION
Wichita, Kansas
District Conservatory Agent

Date 10-7-51

PLUGGING
FILE SEC. 19 TWP. 1 R. 18
BOOK PAGE 114 LINE 34