

8-26 15-147-19042-00-00

6 010630

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 10-9-1960

C NW SE , SEC. 19 , T 1 S, R 18 W/E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5134

Lease Name Schluntz Well # 9

Operator: Graham Michaelis Corp  
Name & Address: Box 232  
Russell, Ks.

County Phillips 116.35

Well Total Depth 3580 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well  Gas Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Co. License Number 5134

Address Same

Company to plug at: Hour: 10:00 AM Day: August Month: August Year: 19 88

Plugging proposal received from Norman Rodie

(company name) Same (phone)

were: Order 400 sks 60/40 Poz 8% Gel 400# Hulls. 4 1/2" casing at 3579'. Perf  
3391' - 3454'. Cast iron plug at 3270'. Squeezed at 1425' w/225 sks  
Squeezed at 1513' and 1613' w/300 sks.

Elev. 2149' Anhydrite 1765'

S.L. Dakota 1150' Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: Day: 26 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 2520'. Pumped in 50 sks cement. Pulled

35 joints. Pumped in 50 sks cement w/100 sks Hulls. Circulated. Pulled tubing  
Tied onto casing pumped in 10 sks cement. Max 750#. Holding. Squeezed down  
8 5/8" 145 sks cement w/300# Hulls. Max 750#. Holding 700#.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If you observe this plugging.)

Signed Dale F. Balthazor (TECHNICIAN) Dale F. Balthazor

DATE 9-22-88

INV. NO. 22361