

6 010556

10-8-8713-147-00137-06-01

API NUMBER 15- 9 - 1956  
NW, SEC. 16, T 1 S, R 18 W/~~E~~  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Lease Name Flory Well # 1  
County Phillips 112.61  
Well Total Depth 3465 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 211

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4807  
Operator: G K M Inc.  
Name & Address Box 520  
Great Bend, Kansas 67530

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor G. K. M. Inc. License Number 4807

Address Great Bend, Kansas

Company to plug at: Hour: \_\_\_\_\_ Day: 8 Month: Oct. Year: 19 87

Plugging proposal received from Jerry Rice

(company name) G. K. M. Inc. (phone) \_\_\_\_\_

were: Perf. Anhdrite and base of Dakota. Order 250 sks cement 65/35 Pozmix 10% Gel  
2% Econolite 500# Hulls 5 1/2 at 3461' Perf 3364' - 3405'.

Elev. 2131' Anhydrite 1745'

Dakota . 1200'

931'

Plugging Proposal Received by D. F. B.  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 8 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing 50 sks cement. Then 100 sks  
cement w/300# Hulls. Max pump pressure 500# closed w/200#. Pumped down 8 5/8" 100 sks  
cement w/200# Hulls. Max pump pressure 400#. Closed w/200#.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1987

Remarks: B. J. Titan Cemented Co.  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED** ~~Observe this plugging.~~

Signed Dale F. Balthazor  
(TECHNICIAN)  
Dale F. Balthazor

DATE 10-20-87

DIV. NO. 18567 10-08 DEC 03 1987

FORM CP-2/3 LR  
Rev. 01-84