

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00920-00-00
Spot: SESWSW Sec/Twnshp/Rge: 16-1S-18W
330 feet from S Section Line, 990 feet from W Section Line
Lease/Unit Name: STAHN A Well Number: 1
County: PHILLIPS Total Vertical Depth: 3510 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATION
Address: 7060 S. YALE #609
TULSA, OK 74136

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 212 125 SX CMT
Production: Size 5.5 feet: 3508 98 SX CMT 114.08
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/24/2001 9:00 AM
Plug Co. License No.: 31154 Plug Co. Name: RICE PRODUCTION COMPANY
Proposal Rcvd. from: GEORGE RICE Company: RICE PRODUCTION COMPANY Phone: (316) 793-2645

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perfs 3380' - 3384'; 3412' - 3417'; 3430' - 3438'; 3440' - 3463'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/24/2001 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Fisher Well Service RIH with tubing to 2800' - pumped 100 sxs 60/40 pozmix with 200# hulls.
Pulled tubing to 2000' - pumped 75 sxs 60/40 pozmix with 200# hulls.
Pulled tubing to 900' - cwc 45 sxs 60/40 pozmix with 200# hulls. Pulled tubing.
Tied onto backside - pumped 50 sxs 60/40 pozmix with 200# - pumped in pressure to Max. P.S.I. 400#. S.I.P. 250#.
Tied onto 8 5/8" casing. PTOH. Squeezed with 35 sxs 60/40 pozmix - pumped in pressured Max. P.S.I. 400#. S.I.P. 200#.
Total 60/40 pozmix 305 sxs with 600# hulls used.

INVOICED
DATE 6-01-01
INV. NO. 2001061876

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 1 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY - TICKET #6228.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

MAY 30 2001

LIVINGSTON OIL

#1 STAHN 'A'

16-1-18w
SE SW SW

Contr. SAUVAGE & DUNN DRIG

PHILLIPS County

E2195 rb Comm. Comp. 8-31-56 IP 25 BOPD

Tops	Depth	Datum
Awh		+408
HEEB	3338	-1113
LANS	3382	-1187
TD	3512	-1317

Casing

8" 212

5" 3511

DST 3370-95/1 HR, 33' 0, BHP 1060#

DST 3395-3420/1 HR, 62' V H OCM, BHP 925#

DST 3419-3560, 5' M, BHP 0#

DST 3440-60/1 HR, 368' 0, 120' SL OCM,

BHP 930#

PERF 3464-63: ACID 1500, SWB 41 B0/5 HRS:

PERF 3412-17: ACID 1500, 66 B0/7 HRS:

PERF 3380-84, 30 B0/2 HRS: SWB 2 BOPH/12

HRS

Nuffstutter

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS