

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00921-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 16-1S-18W
1650 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: STAHN A Well Number: 2
County: PHILLIPS Total Vertical Depth: 3466 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATION
Address: 7060 S. YALE #609
TULSA, OK 74136

Conductor Pipe: Size feet: \$112.65
Surface Casing: Size 8.62 feet: 211 175 SX CMT
Production: Size 5.5 feet: 3465 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/12/2002 10:00 AM

Plug Co. License No.: 31070 Plug Co. Name: EAGLE RIVER ENERGY CORPORATION

Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (316) 793-2645

Proposed: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging: Fish in hole; rods, pump and tubing in the hole.
Method: Casing squeezed at 1876' - 1906' with 230 sxs cement (1984).
Casing squeezed at 1021' - 1051' with 150 sxs cement 1984).

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/13/2002 1:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. Cementers to 5 1/2" casing.
Squeezed 200 sxs 60/40 pozmix plus 500# hulls mixed in cement.
Max. P.S.I. 500#. S.I.P. 300#.
R.U. Cementers to 8 5/8" S.P. Squeezed 50 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED
AUG 21 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-21-02

INV. NO. 2003060305

AUG 15 2002

LIVINGSTON OIL COMPANY

#2 STAHN 'A'

16-1-18W
SW NW SW

Contr. LEWIS DRLG


PHILLIPS County

E 2146RB Comm. 9-28-56 Comp. 11-9-56 IP 50 BOPD

Tops	Depth	Datum
Anh		+408
HEEB	3292	=1146
BR LM	3321	=1175
LANS	3328	=1182
ID	3467	=1321

Casing
 8" 214
 5" 3467
 DST 3326-45/1 HR, 10' M; BHP 0#
 DST 3353-75/1 HR, 60' OGM, BHP 930#
 DST 3393-3415/1 HR, 110' V H OGM, 90' G
 BHP 1120#
 PERF 3405-10: ACID 1500: VTR: SQZ: PERF
 3385-90: ACID 1000: 9. BOPD: PERF 3370-75
 AQID 1500

HUEFFSTUETTER



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS